BUH Interventional Radiology

Healthcare / Refurbishment

Key Features:

- Two-phase enabling and refurbishment project
- Coordination of specialist suppliers
- Completed within a 'live' radiology department

Comprising two distinct phases, this project comprised the modernisation of Basildon Hospital's existing Radiology department.

Firstly, we completed the strip-out and enabling package of works. Works involved isolations, strip-out and minor refurbishment works to form a temporary dirty utility and drug cupboard store. Carried out within an operational Radiology department, we coordinated a robust decant/recant strategy to ensure existing facilities adjacent to the site area could continue to function.

Following our successful coordination of the enabling works, we were awarded the refurbishment and installation phase.

Central to this phase was our close coordination with specialist supplier Siemens for the delivery, installation and commissioning of the new angiography system. A specialist workshop was held with the specialist supplier and the Trust, where the following was discussed and agreed:

- A review was completed of the services design drawings to ensure that they fully matched the specialist's requirements
- The specialist's installation process was fully reviewed and understood and in particular: Specific requirements established in terms of the build process that needed to be completed prior to each specialist commencing / The delivery process was discussed for the equipment in question, size, weight, delivery route and any protection required, most suitable delivery times etc / Commissioning process discussed and understood / Programme of works discussed and understood / How the staff training process was to work, linked to programme milestones

Following the workshop, we had a clear understanding of how Siemens were going to complete their install and could incorporate all aspects within our overall programme.

Client:	Basildon & Thurrock University Hospitals NHS Foundation Trust
Project Value:	£1,600,000
Programme Duration:	28 weeks
Architect:	AD Architects
Quantity Surveyor:	Gardiner & Theobald