Emergency Department

LOGAN CONSTRUCTION

Healthcare / Extension, Refurbishment and Externals

Key Features:

- Multiple areas of the ED refurbished
- Adjacent ED areas remained occupied
- Coordinated through the COVID-19 pandemic

Majors A

Within this phase, we created seven new cubicles. New partitions, doors and decoration combined with refurbished MEP services and ceilings ensured the Trust received the revitalised area they required.

To ensure Majors could maintain suitable facilities for patient care, we programmed two cubicles to be refurbished at any one time. Once these were handed back to the clinical team after completion, we moved onto the next two cubicles.

Owing to the adjacent Resus Unit and Mental Health cubicles, we implemented a robust noise, dust and vibration strategy to safeguard the highly vulnerable patients in care. Real-time site monitoring, underpinned through regular visits by the Trust's Infection Control team, ensured our controls remained suitably robust throughout this phase.

Mental Health and Majors B

Two mental health cubicles, a shower room and WC were fit-out in this phase. Owing to the highly vulnerable patients these facilities would serve, we supplied and installed anti-ligature, anti-pick mastic and anti-tamper elements.

As the clinical team required one mental health cubicle be available at any one time, we programmed these areas sequentially. Underpinning this programme was a methodology which appreciated the highly vulnerable patients being treated adjacent to the cubicle we were working in.

Majors B works provided additional capacity to the existing area. Full height partitions were installed to separate areas and create new cubicles. Additionally, an existing cubicle was transformed into a drugs preparation room and store.

Client:	St George's University Hospitals NHS Foundation Trust
Project Value:	£2,500,000 (Anticipated)
Programme Duration:	80 weeks (Scheduled to Complete 13.05.2022)
Architect:	Hunters
Quantity Surveyor:	WT Partnership